

数 量 計 算 書

仕 様 書 番 号

建工第 29 号

工 事 名

舗装補修工事

工 事 場 所

海津市海津町 深浜・江東 地内
(市道海津11009号線)

令 和 7 年 度

数量総括表

[illegible]

計 算 書										
名 称	計 算 式				単 位	数 量				
【舗装工】										
表層工 再生密粒度As(20) PK-4 t=50mm	面積計算書より	図面より(①)	図面より(②)	図面より(③)						
	A = 1021.1	+	26.9	+	26.4	+	11.2	1,085.6	m ²	1,090
表層工 再生密粒度As(20) PK-4 t=10mm	面積計算書より									
	A = 111.8						111.8	m ²	112	
表層工 再生密粒度As(20) PK-4 平均t=30mm	図面より(④)	図面より(⑤)								
	A = 7.4	+	9.2					16.6	m ²	17
舗装版切断 15cm以下	No.0～No.1 + 8.0	取付部付近	終点							
	L = 28.0	+	6.1	+	7.1	=	41.2	m	41	
路面切削工 As版 平均厚t=40mm	面積計算書より	図面より(①)	図面より(②)	図面より(③)						
	A = 1021.1	+	26.9	+	26.4	+	11.2	= 1,085.6	m ²	1,090
殻運搬 As殻(切削)	V = 1085.6	×	0.04				= 43.4	m ³	43	
	運搬先【TSUCHIYA(株)(養老郡養老町釜段字新開468)】									
	運搬距離 L=8.7km									
殻処分 As殻(切削)	w = 43.4	×	2.35				= 102.0	t		
	処分先【TSUCHIYA(株)(養老郡養老町釜段字新開468)】									
【土工】										
路肩盛土 平均W=25cm	延長	土量/m								
	V = 13.2	×	0.013				= 0.2	m ³	1	
【区画線工】										
白色 実線 W=15cm 溶融式	延長計算書より									
	L = 287.0						= 287.0	m	290	
白色 破線 W=15cm 溶融式	延長計算書より									
	L = 82.5						= 82.5	m	83	

舗装工面積計算書

表層工／路面切削工											
測 点	距 離	幅	平均幅	面 積	摘 要	測 点	距 離	幅	平均幅	面 積	摘 要
No. 0	(m)	(m)	(m)	(m ²)							
+ 0.00		6.80									
No. 1	20.0		6.80	136.0							
+ 0.00		6.80									
No. 1	8.0		6.80	54.4							
+ 8.00		6.80									
No. 1	0.0		6.95	0.0							
+ 8.00		7.10									
No. 2	12.0		7.10	85.2							
+ 0.00		7.10									
No. 3	20.0		7.10	142.0							
+ 0.00		7.10									
No. 4	20.0		7.10	142.0							
+ 0.00		7.10									
No. 5	20.0		7.10	142.0							
+ 0.00		7.10									
No. 6	20.0		7.10	142.0							
+ 0.00		7.10									
No. 7	20.0		7.10	142.0							
+ 0.00		7.10									
No. 7	5.0		7.10	35.5							
+ 5.00		7.10									
			小 計	1021.1							
	145.0		合 計	1021.1							

実線					
名 称	測 点			数 量	摘 要
	左・右	自	至		
白色 実線 W=15cm	左			72.0 m	
	左			75.0 m	
	右			69.0 m	
	右			71.0 m	
合 計				287.0 m	

破線					
名 称	測 点			数 量	摘 要
	左・右	自	至		
白色 破線 W=15cm	中	NO. 0 + 0.0	NO. 7 + 5.0	72.5 m	@5m
	左			5.0 m	@1m
	右			5.0 m	@1m
合 計				82.5 m	