

建工第30号

舗装補修工事

海津市 南濃町 駒野・奥条 地内

§. 1 数 量 計 算 書



## 数量計算書

名 称	計 算 式	単 位	数 量
<b>【舗装工】</b>			
舗装切断 As 15cm以下	<small>交差点北東 終点</small> $L = 2.35 + 3.80$	= 6.2 m	6
舗装版破碎 平均t=50	<small>面積計算書より</small> $A = 390.7$	= 390.7 m <sup>2</sup>	391
殻運搬・処分 As破碎塊	$V = 390.7 \times 0.05$ <small>運搬処分先:TUCHIYAリサイクルセンター(2.4km)</small>	= 19.5 m <sup>3</sup>	20
不陸整正 RC-30,t=15	$A = 390.7$	= 390.7 m <sup>2</sup>	391
表層 再生密粒度As(13) t=50	$A = 390.7$	= 390.7 m <sup>2</sup>	391
<b>【仮設工】</b>			
交通誘導警備員 B	$N = 10.0$	= 10.0 人	10

## 舗装工面積計算書

切削工、路上路盤再生工、表層工						切削工、路上路盤再生工、表層工					
測点	距離	幅	平均幅	面積	摘要	測点	距離	幅	平均幅	面積	摘要
No.	(m)	(m)	(m)	(m <sup>2</sup> )		No.	(m)	(m)	(m)	(m <sup>2</sup> )	
No. 0						No.					
+ 0.00		2.30				+					
No. 1	20.0		2.40	48.00		No.					
+ 0.00		2.50				+					
No. 2	20.0		2.38	47.60		No.					
+ 0.00		2.25				+					
No. 3	20.0		2.25	45.00		No.					
+ 0.00		2.25				+					
No. 4	20.0		2.30	46.00		No.					
+ 0.00		2.35				+					
No. 5	20.0		2.33	46.60		No.					
+ 0.00		2.30				+					
No. 5	15.8		2.25	35.60		No.					
+ 15.80		2.20				+					
No. 5	0.0		2.35	0.00		No.					
+ 15.80		2.50				+					
No. 6	4.2		2.48	10.40		No.					
+ 0.00		2.45				+					
No. 6	7.8		2.83	22.10		No.					
+ 7.80		3.20				+					
No. 7	12.2		3.50	42.70		No.					
+ 0.00		3.80				+					
No.						No.					
+						+					
No.				38.94	No.5+15.8~	No.				△ 0.14	制水弁、仕切弁 計3箇所(控除)
+				7.93	交差点部へロン 交差点部北東	+					
No.						+					
+						+					
							0.0		小計	△ 0.14	
	140.0		小計	390.87			140.0		合計	390.73	