

建工第35号

舗装補修工事

海津市 平田町 野寺 外 地内

数 量 計 算 書

工区①:野寺

[illegible]

工区②：岡

[illegible]

数量計算書						工区①:野寺						
名 称	計 算 式					単 位	数 量					
【舗装工】												
舗装切断 As 15cm以下	L =	起点 (No.0) 6.00	+	No.0~1 北側取付 19.65	+	No.3 北側取付 5.35	+	須賀橋 北側取付 4.85	=	40.35	m	40
	+	須賀橋 南側取付 4.50						=	40.35			
路面切削 平均t=40	A =	面積計算書より 1615.1					=	1,615.1	m ²	1620		
殻運搬・処分 As 切削屑	V =	1615.1 × 0.04 運搬処分先:TUCHIYAリサイクルセンター(9.2km)					=	64.6	m ³	65		
表層 再生密粒度As(20) PK-4,t=50	A =	1615.1					=	1,615.1	m ²	1620		
【区画線工】												
溶融式 白,実線,W=15cm	L =	546.0					=	546.0	m	550		
溶融式 白,破線,W=15cm	L =	55.0					=	55.0	m	55		
溶融式 白,実線,W=45cm	L =	23.5					=	23.5	m	24		
溶融式 矢印・記号・文字 白,W=15cm換算	L =	32.0					=	32.0	m	32		
【仮設工】												
交通誘導警備員 B	N =	15					=	15	人	15		

舗装工面積計算書

工区①:野寺

路面切削工,表層工											
測 点	距 離	幅	平均幅	面 積	摘 要	測 点	距 離	幅	平均幅	面 積	摘 要
No. 0	(m)	(m)	(m)	(m ²)		No.	(m)	(m)	(m)	(m ²)	
+ 0.00		6.00				+					
No. 1	20.0		6.40	128.00		No.					
+ 0.00		6.80				+					
No. 2	20.0		6.53	130.60		No.					
+ 0.00		6.25				+					
No. 3	20.0		6.58	131.60		No.					
+ 0.00		6.90				+					
No. 4	20.0		6.78	135.60		No.					
+ 0.00		6.65				+					
No. 5	20.0		6.68	133.60		No.					
+ 0.00		6.70				+					
No. 6	20.0		6.70	134.00		No.					
+ 0.00		6.70				+					
No. 7	20.0		6.70	134.00		No.					
+ 0.00		6.70				+					
No. 8	20.0		6.73	134.60		No.				13.48	No.11
+ 0.00		6.75				+					取付部
No. 9	20.0		6.78	135.60		No.					
+ 0.00		6.80				+					
No. 10	20.0		6.65	133.00		No.					
+ 0.00		6.50				+					
No. 11	20.0		6.63	132.60		No.					
+ 0.00		6.75				+					
No. 11	18.5		7.58	140.20		No.			控除	△ 1.78	マンホール×5
+ 18.50		8.40				+					仕切弁×3
No.											
+											
	238.5		小計	1603.40			238.5		合計	1615.09	

区画線工延長計算書

白色、実線、W=15cm

工区①:野寺

名 称	測 点			数 量	摘 要
	左・右	自	至		
外側線	左	NO. 0 + 0.0	NO. 11 + 18.5	238.5 m	
	左			△ 3.0 m	控除:横断歩道
	右	NO. 0 + 0.0	NO. 11 + 18.5	238.5 m	
	右			△ 3.0 m	控除:横断歩道
中央線				75.0 m	横断歩道前後、カーブ
合 計				546.0 m	

区画線工延長計算書

白色、破線、W=15cm

工区①:野寺

名 称	測 点			数 量	摘 要
	左・右	自	至		
中央線				55.0 m	@5m×11
合 計				55.0 m	

区画線工延長計算書

白色、実線、W=45cm

工区①:野寺

名 称	測 点			数 量	摘 要
	左・右	自	至		
横断歩道		NO. 10 ~ 11		18.0 m	@3.0m×6
停止線		NO. 10 ~ 11		5.5 m	@2.75×2
合 計				23.5 m	

区画線工延長計算書

矢印・記号・文字、W=15cm換算

工区①:野寺

名 称	測 点			数 量	摘 要
	左・右	自	至		
◇				32.0 m	@16.0m×2
合 計				32.0 m	

数量計算書					工区②:岡	
名 称	計 算 式			単 位	数 量	
【舗装工】						
舗装切断 As 15cm以下	起点 (No.0) L = 6.80	終点 (No.1+10) + 6.45	= 13.25	m	13	
舗装版破碎 平均 t=50	面積計算書より A = 197.1			= 197.1	m ² 197	
殻運搬・処分 As 破碎塊	V = 197.1 × 0.05 運搬処分先:TUCHIYAリサイクルセンター(7.8km)			= 9.9	m ³ 10	
掘削 t=100	V = 197.1 × 0.1			= 19.7	m ³ 20	
不陸整正 RC-30,平均t=20	面積計算書より A = 197.1			= 197.1	m ² 197	
上層路盤 再生瀝青安定処理材(40) t=100	面積計算書より A = 197.1			= 197.1	m ² 197	
表層 再生密粒度As(20) PK-4,t=50	面積計算書より A = 197.1			= 197.1	m ² 197	
【区画線工】						
溶融式 白,実線,W=15cm	区画線工延長計算書より L = 60.0			= 60.0	m 60	
溶融式 白,破線,W=15cm	区画線工延長計算書より L = 15.0			= 15.0	m 15	
【仮設工】						
交通誘導警備員 B	N = 5			= 5	人 5	

舖裝工面積計算書

工区②：岡

[illegible]

区画線工延長計算書

白色、実線、W=15cm

工区②:岡

名 称	測 点			数 量	摘 要
	左・右	自	至		
外側線	左	NO. 0 + 0.0	NO. 1 + 10.0	30.0 m	
	右	NO. 0 + 0.0	NO. 1 + 10.0	30.0 m	
合 計				60.0 m	

区画線工延長計算書

白色、破線、W=15cm

工区②：岡

名 称	測 点			数 量	摘 要
	左・右	自	至		
中央線				15.0 m	@5m×3
合 計				15.0 m	