

建工第36号

舗装補修工事

海津市 南濃町 志津 地内

数 量 計 算 書

数量総括表

[illegible]

数量計算書

名 称	計 算 式	単 位	数 量
【舗装工】			
舗装切断 As 15cm以下	$L = \overset{\text{起点}}{6.00} + \overset{\text{終点}}{6.00} = 12.00$	m	12
路面切削 平均 t=30	$A = \overset{\text{面積計算書より}}{1137.7} = 1,137.7$	m ²	1140
殻運搬・処分 As 切削屑	$V = 1137.7 \times 0.03 = 34.1$ 運搬処分先:TUCHIYAリサイクルセンター(4.4km)	m ³	34
表層 再生密粒度As(20) PK-4,t=50	$A = 1137.7 = 1,137.7$	m ²	1140
【区画線工】			
溶融式 白,実線,W=15cm	$L = 480.0 = 480.0$	m	480
溶融式 矢印・記号・文字 白,W=15cm換算	$L = 48.0 = 48.0$	m	48
【仮設工】			
交通誘導警備員 B	$N = 8 = 8$	人	8

舗装工面積計算書

路面切削工,表層工											
測 点	距 離	幅	平均幅	面 積	摘 要	測 点	距 離	幅	平均幅	面 積	摘 要
No. 0	(m)	(m)	(m)	(m ²)		No.	(m)	(m)	(m)	(m ²)	
+ 0.00		6.00				+					
No. 1	20.0		6.00	120.00		No.					
+ 0.00		6.00				+					
No. 2	20.0		6.00	120.00		No.					
+ 0.00		6.00				+					
No. 3	20.0		6.00	120.00		No.					
+ 0.00		6.00				+					
No. 4	20.0		6.00	120.00		No.					
+ 0.00		6.00				+					
No. 5	20.0		6.00	120.00		No.					
+ 0.00		6.00				+					
No. 6	20.0		6.00	120.00		No.					
+ 0.00		6.00				+					
No. 7	20.0		6.00	120.00		No.					
+ 0.00		6.00				+					
No. 8	20.0		6.00	120.00		No.					
+ 0.00		6.00				+					
No. 9	20.0		6.00	120.00		No.					
+ 0.00		6.00				+					
No. 9	10.0		6.00	60.00		No.					
+ 10.00		6.00				+					
No.						No.					
+						+					
No.						No.			控除	△ 2.32	マンホール×7
+						+					
No.											
+											
	190.0		小計	1140.00			190.0		合計	1137.68	